



# Resurrection Creek

## Stream Restoration Project

Seward Ranger District



Brian Bair  
Project Fisheries  
Biologist

Chugach National  
Forest



Seward Ranger  
District

TEAMS Enterprise  
Unit


Dave Blanchet

Bill MacFarlane


John Lang



# Project Area









Project Area







# History

- Home to one of Alaska's Early Gold Rushes in 1888





Extensive hydraulic and hand placer mining began in 1895 and continued intermittently into the 1950s.



Hydraulic mining provided the power needed to process large volumes of alluvial gravels for gold.



Archives, University of Alaska, Fairbanks



# Past Restoration Planning and Implementation

- ❖ Resurrection Creek Watershed Association  
Hydrologic Condition Assessment  
(Kalli and Blanchet, 2001)
- ❖ Resurrection Creek Landscape Assessment  
Recommended Rehabilitation of the lower 6 river  
miles of stream (USDA-FS, 2001)
- ❖ Resurrection Creek Stream Channel and Riparian  
Restoration Analysis (River Mile 5 – 6.5)  
(Bair, Powers and Olegario, 2002)





- **Steep, Constrained Channel**
- **Mostly riffle habitat**





***Without intervention, poor fish and wildlife habitat conditions will persist, conceivably for centuries***





**Relic Reference  
Reach**

**Disturbed Reference  
Site**

**Project Area**



**Reference Reach**  
**River Mile 8**

**Floodplain**

**Side  
Channels**

**Channel**





# CHANNEL MORPHOMETRY

## RESURRECTION REFERENCE REACH

|                              |  |
|------------------------------|--|
| Valley Length                | 814 feet   |
| Valley Slope                 | 0.02 (2%)  |
| Valley Width                 | 705 feet   |
| Channel Length               | 1404 feet  |
| Elevation Drop               | 16 feet  |
| THALWEG SLOPE                | <b>0.0117 (1.17%)</b>                                |
| Riffle Slope                 | 0.015 (1.5%)   |
| Rosgen Channel Type          | C3-4   |
| Bankfull Width               | 55.0 feet  |
| Bankfull Ave. Depth          | 1.8 ft.  |
| SINUOSITY                    | 1.7  |
| LARGE IN-STREAM<br>WOOD/MILE | <b>346 PIECES</b><br><b>(&gt;12 IN. IN DIAMETER)</b> |
| ENTRENCHMENT RATIO           | 7.9  |
| POOLS/MILE                   | 19   |
| D50                          | 98mm   |
| Length of Meander            | 371-551 feet   |
| Belt Width                   | 197-295 feet   |
| AVE. BED SHEAR STRESS        | 6.3-8.3 KG/M <sup>2</sup>                            |





# Restore fish habitat by increasing:

- Pools from 3 to 23 per river mile
- Side channel flow from  $<1\%$  to  $20\%$ .
- Large in-stream wood from 8 to 330 pieces/river mile
- Spawning gravel from 160 to 2,000 yd<sup>2</sup> per river mile

- Resurrection Creek EIS (Chugach National Forest and TEAMS, 2003-2004)

## Final Environmental Impact Statement

Resurrection Creek Stream and Riparian Restoration Project

Seward Ranger District, Chugach National Forest  
Kenai Peninsula Borough, Alaska



November 2004

R10-MB-539



- Contracting and Implementation 2005-2006





# Resurrection Creek Stream Restoration





~1.4 Mile Stream

North and Downstream

~1.3 Miles Side Channels

~160,000 yd<sup>3</sup>

June 6, 2002

60 Acres of Flood Plain

June 6, 2002

July 10, 2006

July 10, 2006

\$990,000

2002 photo with  
new 2005-6 stream channel  
features mapped on

2002 Photo  
with new 2005-6  
stream channel  
features mapped on

**Legend**

2005 Major stream diversions

2005 Side channels


2006 New channels carrying more than 20% of flow

2006 New side channels carrying less than 15% of flow

0 1,000 feet 2,000 feet



# General Implementation Strategy

































# Reference Reach Side Slough Logjam Entrance





# Reference Reach Side Slough Logjam Entrance





# Reference Reach Side Slough below Logjam









May 10, 2005

# Construction Sequence “Meander 2”





May 25, 2005

# Construction Sequence “Meander 2”





June 15, 2005

# Construction Sequence “Meander 2”





# Construction Sequence “Meander 2”


June 28, 2005





July 6, 2005


# Construction Sequence “Meander 2”





Nov 9, 2005


# Construction Sequence “Meander 2”





Sept 22, 2006


# Construction Sequence “Meander 2”





August 31, 2007

# Construction Sequence “Meander 2”












Approximate number of fish at peak of run

This image shows a wide river with a dark, rocky bed. The water is calm, reflecting the surrounding environment. On the right bank, there is a dense forest of evergreen trees. The text "Approximate number of fish at peak of run" is overlaid in yellow.




Data from Chugach National Forest fisheries






## Approximate numbers of fish at peak run


### Pinks




### Chum



### Chinook



### Coho







**Adult Chinook Salmon Locations  
Mid to Late in Run – August 3, 2006**





## Legend



**Adult Pink Salmon Numbers by Location**  
**Peak of Run – August 17, 2006**



# Thank You

[http://www.fs.fed.us/r10/chugach/news\\_releases/res\\_creek\\_rest.html](http://www.fs.fed.us/r10/chugach/news_releases/res_creek_rest.html)